

**Supplier Quality Control
Requirement**

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 2 / 26

CONTENTS

1. GENERAL	3
1.1. Intent and Scope	3
1.2. Definition	3
1.3. Supplier's Responsibility	4
1.4. Right of Access by Inspector	4
1.5. Safety	4
1.6. Test Facility	5
1.7. Audit Verification	5
2. WORK CONTROL	5
2.1. Sub-Supplier Control	5
2.2. Calibration Control	5
2.3. Control of Identification and Traceability	5
2.4. NDE Personnel	5
2.5. Supplier's Inspector	5
3. STATUTORY REQUIREMENTS	6
4. INSPECTION AND TEST	6
4.1. SUPPLIER'S QC PLAN	6
4.2. INSPECTION AND TEST INSTRUCTIONS TO SUPPLIERS	6
4.3. SUPPLIER'S INSPECTION AND TEST PLAN	16
4.4. FABRICATION AND TESTING PROCEDURES/INSTRUCTIONS	19
4.5. PRE-INSPECTION MEETING (PIM)	19
4.6. INSPECTION NOTIFICATION	20
4.7. Hold Points	20
4.8. Concession Request	20
4.9. Non-Conformity Report	20
4.10. Certificate of Conformance by the Supplier	21
4.11. Inspection Release by the Contractor	21
5. DOCUMENTATION	21
5.1. Inspection Documents at Delivery	21
5.2. Documentation	21
6. JOB SPECIFIC REQUIREMENTS	22
6.1. Safety Quality License for Boiler and Pressure Vessel	22
6.2. Positive Material Identification	22
6.3. Welding & NDE of Pressure Vessels, Heat Exchangers, Coolers, Boilers and Heaters (Including Piping of Packaged Units)	22
7. ATTACHMENTS	22
ATTACHMENT 1 INSPECTION RELATED DOCUMENTATION	23
ATTACHMENT 2 STATUS OF SUB-ORDERED MATERIAL	25
ATTACHMENT 3 FORMAT OF INSPECTION AND TEST PLAN	26

Supplier Quality Control Requirement

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 3 / 26

1. GENERAL

1.1. Intent and Scope

This specification covers quality control requirements to be fulfilled by Supplier for the equipment and materials which are procured by the Contractor. The Supplier shall perform the inspection and related quality control work in accordance with this specification and the Specifications included in the Purchase Order.

1.2. Definition

GOODS	A generic term describing materials, equipment, products, supplies spares, documentation data, computer programs, labor(construction, design, maintenance, supervision), or other deliverables provided by a supplier. Whenever appropriate, items and products are also used.
SUPPLIER	The company or organization which supplies the goods and services
SUB-SUPPLIER	The company or organization which supplies goods to Supplier.
RoK	Republic of Kazakhstan
COMPANY	Karabatan Utility Solutions LLP.
CONTRACTOR	A firm awarded with a contract by COMPANY to provide Engineering/Procurement for the PROJECT
PROJECT	The Karabatan Power Plant
PO	Purchase Order
INSPECTOR	Person, who is Contractor's own employee or from inspection agencies, will execute inspection activities on behalf of Contractor
SNCR	Supplier Non-conformity Report
PMI	Positive Material Identification
IRN	Inspection Release Notice
SRN	Shipping Release Notice
SNCR	Supplier Non-Conformity Report

Supplier Quality Control Requirement

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	4 / 26

1.3. Supplier's Responsibility

- 1.3.1.** Supplier shall develop and implement specific Quality Management System which shall be in full compliance with ISO 9001:2008 requirements. Preference shall be given to proposal with ISO 9001:2008 certification, though certification to ISO 9001 is not mandatory. Supplier shall continually improve its quality management system and maintains its effectiveness in accordance with ISO 9004: 2009 requirements.

COMPANY and CONTRACTOR have rights to visit Supplier for inspection and review or audit.

Supplier shall develop a corrective action where inspection and review or audit results in a failure to meet stated requirements. The plan shall ensure delays to the construction schedule are minimized.

This inspection could not be used as a proof of Supplier's effective control over the product quality. The inspection (review or audit) by COMPANY and CONTRACTOR doesn't release Supplier from its responsibility to supply acceptable products and restrict the CONTRACTOR reject the products.

ISO Standard:

- ISO 9000: 2005 "Quality Management Systems – Fundamentals and Vocabulary"
- ISO 9001: 2008 "Quality Management Systems – Requirements"
- ISO 9004: 2009 "Quality Management Systems-Guidelines for Performance Improvements"

- 1.3.2.** The Supplier shall be responsible to perform all inspection and tests required for the equipment and materials which he fabricates/manufactures in accordance with the Purchase Order, and applicable codes and standards.
- 1.3.3.** The Supplier shall assure to disseminate all the requirements for his fabrication and inspection/test thereof down to the Shop Work level and/or sub-suppliers involved in his supply of the purchased Equipment and Materials.
- 1.3.4.** The Contractor's inspection release shall not be meant to relieve the Supplier of any responsibility or liability to ensure that the requirements of Purchase Order are met in all respects to quality even if defective design, material or workmanship is discovered later.

1.4. Right of Access by Inspector

- 1.4.1.** The Inspector shall have the right of free entry for auditing and/or inspection at all reasonable times to the shop where fabrication or testing on the equipment and material is being performed.
- 1.4.2.** The Inspector shall have the right to witness the inspection and tests of the items so specified in the Purchase Order or items agreed mutually.
- 1.4.3.** The Supplier shall provide the latest Supplier documents and drawings as per Inspector's request during his shop inspection work.

1.5. Safety

The Supplier is to provide a safe working environment for Inspector and to alert the Inspector of potential hazards. If the working conditions are unsafe, in the opinion of Inspector, he may not perform his work.

Supplier Quality Control Requirement

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	5 / 26

1.6. Test Facility

Necessary equipment and facilities required for specified inspection or tests shall be provided to Inspector by the Supplier free of any charges.

1.7. Audit Verification

1.7.1. The Supplier's QA/QC manual shall be submitted for Contractor's review when requested in the Purchase Order

1.7.2. The Contractor shall have a right to conduct a QA/QC audit if the Contractor needs verify Supplier's and/or Sub-Supplier's QA/QC work control.

2. WORK CONTROL

2.1. Sub-Supplier Control

The Supplier shall submit Sub-Supplier list, who undertake fabrication of the equipment and materials partially or all, for Contractor's approval. Further, the Supplier shall control Sub-Supplier's QC/Inspection and shall provide Sub-Supplier's with the necessary Specifications and instructions.

Any and all Sub-Supplier's shall be required to have a QC system in place and their QC manual shall be submitted for prior approved if the Contractor deemed it necessary to review.

2.2. Calibration Control

The Supplier shall establish and maintain the procedures of Supplier's calibration control system describing the activities and responsibilities for the control, calibration and maintenance of inspection, measuring and testing equipment used to determine the acceptability in part or in full or a product.

2.3. Control of Identification and Traceability

The Supplier shall establish the procedure that materials supplied/fabricated are fully identified by legible marking through all stage of manufacturing and fabrication.

These identifications and marking details shall be correlated to the certificates or documents so that the Contractor can satisfy the material traceability system. Material maps shall be provided to indicate the identification to the relevant drawings.

2.4. NDE Personnel

Non Destructive Examination shall be performed by qualified personnel certified by an authorized organization. Control and evaluation of NDE including RT film review shall be appropriately performed by level III ASNT, or equivalent. The Supplier shall maintain the qualification list of NDE personnel and present their certificates for review upon request of Inspector.

2.5. Supplier's Inspector

The Supplier's inspector shall be of enough skills and knowledge, and well trained for the inspection and test required. The Supplier shall ensure their qualification, and results of inspection/test inspectors shall be any time reviewed by the Contractor, if deemed required.

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	6 / 26

3. STATUTORY REQUIREMENTS

The Supplier shall arrange and fulfill any work of Statutory Requirements by local regulation which is specified in the Purchase Order at his responsibility and expense.

4. INSPECTION AND TEST

4.1. Supplier's Qc Plan

The Supplier shall submit a detailed Quality Plan specifically developed to the requirements of the Purchase Order within the period stipulated in the requisition. This plan shall integrate the practices and procedures contained in the Supplier's Quality Control System with the Purchase Order requirements.

The Quality Plan shall include, but not limit to the following:

- A complete listing and description of all Quality Control activities to be performed including shop fabrication design, procurement, material handling, factory tests, control of welding processes, non destructive examination and documentation, etc.

Supplier's compliance with the Quality Plan will be verified during manufacturing by Contractor Quality Representative.

4.2. Inspection And Test Instructions To Suppliers

4.2.1. GENERAL

Contractor has the responsibility for the shop inspection of all material and equipment pertaining to Project.

However, Contractor's surveillance or inspection activities are not intended to substitute or to supplement Suppliers Quality Control organization in the performance of their duties.

Suppliers, and their Sub-Suppliers, shall always ensure the fulfillment of the requirements of Purchase Order, Code and Job Specifications through the implementation of their Quality Assurance system of procedures, irrespective of whether or not CONTRACTOR will inspect or witness tests.

Contractor's inspection supervisor, as well as their designated inspectors, shall be granted free entry to the Supplier's shops and to the Sub-Supplier's shops. All necessary assistance shall be afforded to help them in performing their inspection activities, including free use of Supplier's test control equipment and instruments. The same shall be granted to the COMPANY personnel or representatives appointed by the COMPANY

4.2.2. CORRESPONDENCE & DOCUMENTATION

4.2.2.1. Addressee of Inspection and Expediting related correspondence and documents

All correspondence relating to inspection, all inspection notifications and all correspondence relating to expediting, and all documents indicated in the following point 4.2.2.2 shall be addressed as follows:

ADDRESS of your relevant responsible department

Attn: Inspection & Material Management

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	7 / 26

Coordinator NAME

Phone: (*****), **Fax:** (*****), **Email:** (*****)

4.2.2.2. Inspection related documentation

See ATTACHMENT 1 Inspection Related Documentation.

4.2.3. INSPECTION

4.2.3.1. Material or Equipment Subject to Inspection

Material and equipment shall be tested as required in the material requisition, job specifications or applicable codes and international standards (e.g. non-destructive examination, pressure test, performance test, positive material identification etc.).

Contractor will reserve the right to inspect at Supplier's shop all material and equipment purchased for the Project, even items or material defined as "not requiring inspection" elsewhere in the order documentation, if so deemed necessary for any reason.

4.2.3.2. Quality Control Plan (QCP)

Supplier shall prepare a detailed QCP (otherwise called Inspection and Test Plan (ITP) that shall be sent to the Inspection Coordinator at the same time as the first issue of drawings. This plan will be reviewed by Contractor to check that the test plan complies with the requirements of material requisition, job specifications and Codes or international standards applicable to the order. As result of the review Contractor will send back a letter of comments (if any) and the QCP marked- up with the inspection points [hold (H), witness (W) and review (R)].

In the cases of sub-ordered sub-assemblies this procedure may also apply to Sub-Supplier, and the main Supplier will have the responsibility to obtain this documentation timely and transmit it to Contractor.

4.2.3.3. Notification

Notification of readiness for inspection shall be given at least ten (10) working days prior to the inspection date. In addition, for Fabricated Items (like pressure vessels etc.), Supplier will have to notify the actual date when fabrication will start.

It is Supplier's responsibility, in the event of over-time work, weekends and holidays, to give sufficient advance notice in order to allow for proper inspection arrangements.

4.2.3.4. Miscellanea

Progressive inspection may be carried out at various stages in production or manufacturing, in order to monitor compliance with defined requirements and to observe that the right fabrication procedures are applied and adhered to.

The completed vessel or fabricated equipment, or packaged item, may also be inspected prior to painting and preparation for shipment.

Mill test report and/or code forms, required by the order or pertaining to inspection, must be available for the inspectors at the time of final inspection.

Before commencing with any repairs that may affect equipment integrity or operation, Supplier will have to issue to Contractor a repair procedure and obtain their approval.

Materials and equipment that are subject to inspection and are shipped without

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	8 / 26

Contractor inspection, or waiver thereof, will be rejected.

Contractor will notify in writing before shipment the acceptance of the equipment or material by means of an Inspection Release Notice (IRN) issued to Supplier by the Inspection Coordinator. In all cases when transportation is at Supplier's care, shipment is not allowed until Logistics Coordinator will issue a Shipping Release Notice (SRN).

4.2.3.5. Documentation for Inspection

One copy of the latest revision of drawings of the Supplier, or Sub- Suppliers, reviewed and stamped by Contractor shall be available to the Inspectors and/or their delegates at shops. Furthermore one copy of all documents required in the purchase order must be available at the time of final inspection.

Inspector will not perform the inspection and will not release any material or equipment if the proper documentation is not available.

The drawings and documents shall be re-issued to Contractor in the final "as-built" revision, should this need be detected as a result of the checks done during the final inspection.

Supplier (or Sub-Suppliers) welding procedure specifications (WPS) and procedure qualification records (PQR) must meet the requirements of the Material Requisition and Contractor applicable Job Specification.

All welding procedure specifications and procedure qualification records must be sent to Contractor specialty engineer prior to start any welding.

Contractor Inspector shall review the qualification test records of welders and/or welding operators during the inspection visits.

4.2.3.6. Waiver of Inspection

After receipt of notification, Contractor will advise Supplier in writing whenever the inspector will not attend. Written notice will also be given whenever Contractor will decide to waive inspection, partially or totally, for material otherwise subject to inspection.

Test reports and certificates relevant to tests not witnessed must, in any case, be prepared by Supplier's QC organization for review by the Inspector

4.2.4. NON-CONFORMITY

Contractor inspection supervisors, as well as their designated inspectors, shall have the right to reject any material or equipment found to be defective, or showing poor quality of workmanship or that is not in conformity with order requirements. In such cases Inspectors will issue SNCR (Supplier Non-conformity Reports) to Supplier or their Sub-Supplier.

Upon receipt of the SNCR Supplier shall either take immediate action to replace the defective part or component, or advise Contractor in writing on proposed corrective action, or issue a concession request asking for the acceptance of a deviation.

Corrective actions implying repair activities shall be covered by a procedure that must be sent to Contractor for review. No repairs may be started prior to the receipt of Contractor release relevant to the repair procedures.

When concessions have been approved, or corrections have been completed and the achievement of full compliance with the order requirements have been verified,

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	9 / 26

Contractor's Inspection Coordinator will transmit to Supplier the "clearance" or resolution of the pending SNCR.

No equipment or material will be finally accepted unless all pending SNCR are not cleared.

4.2.5. COSTS FOR TESTING

All costs connected with tests and chemical analysis, required by the specifications and drawings, whether conducted by the Supplier, by Laboratories or other testing agencies, including supply of relevant test reports in the required number of copies, shall be at Supplier care.

This requirement is also applicable in all the cases, if any, for which "Positive Material Identification" (PMI) tests are required.

Supplier is advised that whenever material cannot be easily identified and traced to certificates, Contractor will require additional material qualification tests that will have to be carried out at Supplier's cost. The type of tests will be defined by Contractor as appropriate.

4.2.6. SUB-ORDERED MATERIAL OR COMPONENTS

Inspection may also be done at source of supply of equipment and/or materials from Sub-Suppliers or Sub-sub-suppliers.

The form "Sub-Order Status", that is an integral part of this Inspection and Test Instruction, shall be filled-in by Supplier with the list of material or fabricated items to be purchased, and shall be sent to Contractor within 4 weeks after the order placement. However, Supplier's own forms showing at least the same information as Contractor "Sub- Order Status" may be accepted.

Contractor will establish which material, among the ones listed, will be inspected at the source of supply.

Supplier's sub-orders (and sub-sub orders, if any) for materials requiring inspection must include the clause of Contractor inspection (see Para 4.2.1) that must clearly state that material will have to be tested and inspected at source by Contractor.

Each sub-order shall be identified with the following references and information:

- a) Company Name (*****) Project Name (*****) Plant Location (*****)**
- b) Contractor Contract Number (*****)**
- c) Main P.O. Number or Supplier's Job Number**
- d) Full address of the point of inspection**
- e) Sub-Supplier/Sub-sub supplier Job number**

Sub-orders (and sub-sub orders, if any) shall be written in English language, shall clearly describe the materials or equipment purchased and the applicable technical requirements, and shall include all the applicable inspection and testing requirements.

4.2.7. MATERIAL AND TEST CERTIFICATES

4.2.7.1. General

The number & type of copies of certificates, as well as the timing required, is specified in the table at paragraph 4.2.2.2.

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	10 / 26

Suppliers must be aware that certificates of conformity relevant to the applicable Republic of Kazakhstan Codes and Regulations, certificates and inspection dossiers, installation, operation and maintenance instruction manuals, constitute a fundamental part of the supply. The contractual obligations set forth in the purchase order shall not be considered fulfilled, and payments will not be released, until the proper documentation is received by Contractor. The documentation shall be correctly identified with all project information, and shall be traceable to each single lot of quantity of material requisition and item.

4.2.7.2. CERTIFICATION FOR BULK MATERIAL

Material and test certificates (i.e. mill certificates of base material) for pressure bearing parts shall be, as a minimum, type 4.2.3.1 as specified in the standard EN 10204. However, in the case of pressure components under the rules of the PED, the Supplier shall either operate a quality system certified by an independent authority accredited in RoK State Standard Committee (copy of the QA system certificate shall be provided to Contractor), or otherwise shall supply all material certificates as a minimum 3.2 type as per standard EN 10204 or relevant standards described in each Material Requisition.

For structural steel components the certification shall be according to the applicable codes, standards and RoK rules for civil construction.

For bulk material of any kind (piping, valves, fittings, steel shapes for structures, field instruments, electrical cables etc.) the certification supplied must be traceable to Contractor references.

In the cases when the supply of one item is split in lots of quantity, the certificates shall also be traceable to the individual lot.

The certificates must be collected in a booklet or binder, with an index having a cross reference to Contractor material requisition number and item number or position, properly divided according to the index sections.

Certificates that do not comply with the above requirement will be discarded and the supply will not be considered complete. Payments will not be released until the receipt of new sets complying with the criteria set forth here above.

If copy of the required documentation is not available at the time of final inspection, Contractor will not issue the "Inspection Release Notice".

To make the production of the traceability index easier, Contractor may supply Supplier with a table in excel format that will be sent by email every time a lot of material will be released. This table is pre-filled in with material requisition numbers, revision, description, quantity and order delivery date of all items in order.

Supplier shall fill-in the column "Remarks" with the material certificate number pertaining to the lot of quantity of each specific item of material requisition.

4.2.7.3. IMPORTANT NOTICE ON CERTIFICATION FOR BULK MATERIAL

Supplier must be aware that material delivered to site without the relevant certification cannot be delivered to the erection contractors for installation, and is therefore almost useless.

Then Supplier MUST always forward a copy of the certificates together with the material. While this requirement is to be considered valid for all type of bulk material, we recognize that there may be practical problems to strictly comply with this requirement for pipes.

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	11 / 26

For this kind of material the lots normally involve the shipment of several truck loads. In this case the separation of the certificates for each truck will not be easy.

To overcome this problem we require that the complete set of certificates, together with all relevant packing lists, is sent by express courier to the site to the attention of the Construction Manager and/or warehouse coordinator (names, telephone, faxes, e-mail shall be advised as soon as possible) every time a lot of pipes is released for shipment.

The mailing of the certificates shall be done through an express courier, and the identification number of the shipment shall be e-mailed to the Inspection Coordinator.

If the certificates are not ready, Supplier is NEITHER AUTHORISED to SHIP THE MATERIAL, NOR to INVOICE THE RELEVANT AMOUNT.

The date of delivery for penalty calculation purposes shall be the date of the arrival of material TOGETHER with the certificates.

Should the certificates be sent at a date later than the one of material, then the penalty will be calculated based on the date of arrival of certificates.

The packing list for each shipment shall have a line named "Set of material certificates". Copy of the packing list shall be sent to Contractor to the attention of the Inspection Coordinator.

It is mandatory, to optimize the material management data base of the site warehouse, that the packing list relevant to every shipment always bear the IRN number.

4.2.7.4. SPECIFIC REQUIREMENTS FOR CERTIFICATES OF PIPING FITTINGS OF WROUGHT STEEL OF ANY ALLOY

The supplier of the fittings must always supply, in addition to his own material and test certificates, also the material and test certificates of the mill producing the original material, i.e. steel plates for the welded fittings, and pipes for seamless fittings.

The pipe or steel plate mill certificate shall clearly bear the fittings manufacturer name and order number. Contractor's inspector reserves the right to request Supplier to show the unpriced sub-order relevant to plates or seamless pipes.

4.2.7.5. CERTIFICATION FOR FABRICATED EQUIPMENT (ITEMIZED)

What is here indicated normally applies to equipment like pressure vessels and tanks, columns and reactors, heat exchangers, boilers and refinery heaters, packaged units, machines like pumps, compressors, turbines, safety valves, etc. The technical documents attached to each purchase order contain the detailed information pertaining to the type of test certificates to be supplied by Supplier for each category of equipment.

Material and test certificates for pressure bearing parts, main parts of machinery, like for example forged shafts, rotors, impellers, casings, connecting rods, crankshafts, etc., foundation bolts for critical machines like compressors, turbines, that are supplied by the machine fabricator, shall be, as a minimum, type 3.1 as specified in the standard EN 10204 or relevant standards described in each Material Requisition.

For the above components Supplier/Sub-supplier must keep the traceability, and the relevant heat number is to be punched on each piece.

In the case of pressure equipment under the rules of the PED, the Manufacturer of the material (plates, forgings, pipes, etc.) shall either operate a quality system certified by an independent authority accredited in RoK State Standard Committee (copy of the QA system certificate shall be provided to Contractor), or otherwise the certificates shall be

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	12 / 26

3.2 type as per standard EN 10204 or relevant standards described in each Material Requisition.

The certification for fabricated equipment shall be collected in “Inspection Dossiers” booklets (one for each equipment) that will have to include, as a minimum and as applicable, what follows:

- Index of content
- Copy of the last issue of general arrangement drawings and data sheets
- Copy Certificate of Conformity, Certificate of Type, Permit to Use, etc issued by the applicable Regulatory Authorities of Republic of Kazakhstan.
- Copy of the “Installation, Operation and Maintenance Instruction Manual” for pressure equipment under the applicable codes, duly signed by Supplier Project Manager, in Russian and in English languages.
- Manufacturer’s report as per ASME Sect. VIII as applicable
- Copy of the equipment tag plate
- NCR’s, if any, and supporting documentation for their clearance
- Key drawing with reference table to trace the individual certificates
- Mill certificates for all material of construction (e.g. plates, pipes, forgings, castings etc.)
- Quality control plan
- Welding map
- Welding procedure specifications and qualification reports
- Test procedures
- Key map for all NDE tests carried out (e.g. X-ray, UT, Dye Penetrant, Magnetic Particle)
- Test report for all tests carried out (e.g. NDE, pressure test, performance,, running, etc.)
- Heat treatment procedures and heat treatment charts
- Certificates of qualification for welders and NDT operators
- Supplier dimensional check report
- Inspection Release Notice

The “Inspection Dossiers” will have to bear the reference to Contractor project and order number, material requisition number and equipment tag number.

The “Installation, Operation and Maintenance Instruction Manual” applicable to the specific item, required by Contractor and duly signed by Supplier Project Manager, shall be sent to Contractor Inspection Department separately as soon as ready together with the certificates as indicated in the following paragraph.

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	13 / 26

4.2.7.6. CERTIFICATES OF APPROVAL Authorized Bodies

In addition to the number of copies required as for all other documentation, or included in the “Inspection Dossiers”, one copy of equipment/materials applicable certificates shall be supplied separately to Contractor Inspection Department.

The certificates must include all the information required by the relevant codes, including the code number of the Authorized Body. The person signing Supplier’s documentation shall have the relevant power of attorney within Supplier’s organization, and his name and the relevant title shall be clearly readable.

4.2.8. INSPECTION BY AUTHORIZED BODY

It shall be Supplier’s responsibility to make application and to deal with the Authorized Body for their undertaking of design calculation review and appraisal, shop inspection activities and to obtain the final official certification.

All communications with the Authorized Body and the coordination and organization of their inspection activities shall be completely at Supplier’s care and shall not interfere in any way with Contractor inspection.

4.2.9. EXPEDITING

4.2.9.1. General

Contractor will monitor and expedite Supplier during all phases of job development till the delivery of the goods ordered. Expediting activities will consist in desk expediting through phone and letter contacts or, as needed, in visits at Supplier covering the review of all the aspects of the job, i.e. engineering, procurement and fabrication.

4.2.9.2. Contacts

Supplier will have to advise the following information within 2 weeks from order receipt:

- Supplier Job Number (s)
- Job Coordinator Name
- Quality Control Coordinator Name (if different from the above)
- Address of the workshop (s) where the equipment will be manufactured
- Phone, Fax, email

Main Supplier will have to supply, as early as possible, the same information for Sub-Suppliers of material subject to inspection.

Contractor may also decide later on to expedite directly Sub-Suppliers for sub-supplies that may become critical, even if inspection is not required. In these cases Supplier will supply the above information to allow organizing the visits.

4.2.9.3. Job Planning

a) Bulk material

Supplier shall send, within 3 weeks from order, the job schedule covering, at least and as applicable, the phases of engineering, procurement of raw material and fabrication.

b) Equipment or packaged units

Supplier shall send, within 4 weeks from order, detailed schedules, one for each tag,

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	14 / 26

covering engineering, procurement of material, fabrication, testing and transportation (if included).

In case of package units with complex sub-assemblies that are sub-ordered, then the main Supplier will have to obtain from sub-suppliers detailed schedules relevant to their portion of supply.

The schedules for equipment and packaged units shall be done on Microsoft Project 98 electronic files, and shall be updated at least monthly showing planned and actual status of each task. The breakdown of the tasks in the schedules, and their relative connections, shall be conceived in sufficient detail to clearly show the logic of the fabrication process.

4.2.9.4. Job Status Report

a) Bulk material

Supplier shall supply regularly with an agreed frequency, but not less than every three weeks, the information described here below. This information shall be supplied by filling-in a table in excel format that will be sent by Contractor by email. This table is pre-filled with material requisition numbers, revision, description, quantity, and order delivery date of all items in order. Supplier shall fill it in with the information he is originating, i.e. forecast (promised) delivery date, Supplier reference (internal job number), sub-order number and sub-Supplier (if any), remarks (if any, for example quantity and delivery date relevant to sub-lot quantity that could be delivered in a different date, or other relevant information). The table is protected, and the cells to be filled-in by Supplier are clearly indicated by a light yellow color background. The data shall be input in the format indicated in the column headers.

b) Equipment or packaged units

Irrespective of Contractor expediting effort, Supplier shall issue monthly a Job Status Report in electronic file format. Depending on the development of the Job, Contractor Inspector may request later on to modify the frequency of issue.

The Job Status Report shall contain all the information needed to offer a clear picture of the progress in all areas. The topics covered shall be at least the ones listed here below:

- Status of Documents and Procedures
- Status of Sub-Orders and in-house material
- Progress of Fabrication
- Areas of concern
- Action list

The Job Status Report shall include as attachments the Sub-Order list, Job Document Control list, Fabrication Schedule, and any other document deemed appropriate to complete the picture. Each specific topic shall be covered with a brief narrative highlighting the main achievements and problems (if any), and indicating the areas of concern and the relevant action required. The concept is that the narrative shall summarize the analysis done by the Supplier's Project Manager or Job Co-coordinator on all the aspects. This report shall include a table showing the % actual progress achieved versus the planned one for each one of the following areas:

Supplier Quality Control Requirement

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 15 / 26

- Engineering
- Procurement
- Status of raw material or components available
- Fabrication

The basis for calculating the progress achieved shall be the following:

- Engineering
List of deliverables, weighted by man-hours, with two steps:
 - Issue for comments weight 30%
 - Issue for construction weight 70%
- Procurement
List of material to be purchased weighted by value
 - Material requisition issued for inquiry weight 10%
 - Order issue weight 90%
- Status of raw material or components available
List of material weighted by value
 - Delivery at shop weight 100%
- Fabrication
- List of tasks weighted by man-hours

4.2.10.INSPECTOR'S SAFETY

4.2.10.1. General

To comply with the rules and/or to local equivalent laws that establish rules governing the safety subject, and with the purpose of safeguarding the health and safety of Contractor Personnel doing activities at Supplier's premises (e.g. inspection visits, expediting checks etc.), Supplier s are requested to give to visiting Contractor personnel, possibly in writing, the following information:

- Any possible risk for health and safety incurred when operating at Supplier's premises.
- Prevention and protection measures and individual protection means or equipment that Supplier specifies to cope with the risks foreseen.
- Procedures relevant to fire protection and firefighting, evacuation of personnel in case of serious and immediate danger, rescue, first aid and procedures for the management of emergency.

Should the situation be modified in such a way as to change the possible risks for Contractor personnel, it will be Supplier's duty to update the information formerly given with the new risks and the relevant prevention and protection measures.

The Supplier is not relieved, by complying with the above request, from the due

**Supplier Quality Control
Requirement**

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 16 / 26

diligence in the surveillance on Contractor's personnel presence.

Contractor personnel will be obliged to strictly comply with Supplier's safety rules, except when these rules are in conflict with the Law or Contractor safety standards.

4.2.10.2. Inspection In Confined Spaces

During the checks carried out in confined spaces, like for example inside pressure vessels, Supplier shall pay special attention to the aspects that constitute potential risks for the people involved:

- The air changes shall be enough to guarantee a healthy environment, particularly when using sprayed substances for dye penetrant or magnetic particles test
- The people operating inside the confined space shall always be assisted by someone standing in a safe location outside the space itself, who will have to monitor that everything is in order and could call for aid if needed

4.2.11. STATUS OF SUB-ORDERED MATERIAL

See ATTACHMENT 2 Status of Sub-Ordered Material

4.3. SUPPLIER'S INSPECTION AND TEST PLAN

The Supplier shall submit written Inspection and Test Plan for each equipment/material for Contractor's approval. The attached Inspection and Test Plan (ITP) form is to be mandatory followed by Supplier or its Sub-Supplier to ensure conformity across the overall PROJECT.

See Attachment 3 Format of Inspection and Test Plan

Instructions and guidelines for ITP preparation are provided.

4.3.1. Document No. and Rev.

Each Inspection and Test Plan shall be uniquely identified. The ITP number and revision shall be identified.

4.3.2. Date

This shall be the date of issue of the ITP in the numeric format Dd-Mmm-yyyy.

4.3.3. Page

This shall show the quantity of pages in the numeric format xx/yy.

4.3.4. Prepared By

The printed name and original signature of the person preparing the ITP shall appear in this box. Where the ITP is prepared by a Sub-Supplier the Prepared By name and original signature shall be the Sub-Supplier person who prepared the ITP. Otherwise this shall be the Supplier's person who prepared the ITP. The requirement/acceptance criteria is the governing document that is used to ensure that the work is fabricated correctly.

4.3.5. Approved By

The printed name and original signature of the person approving the ITP shall appear in this box. The approval name and signature shall not be the same as that of the person that prepared the ITP. This shall be the Supplier's person who will be responsible for approving the Supplier's and Sub-Supplier's ITP's.

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	17 / 26

4.3.6. Contractor App.

The printed name and original signature of the CONTRACTOR'S REPRESENTATIVE person approving the Supplier's and/or Sub-Supplier's ITP.

4.3.7. COMPANY's REPRESENTATIVE App.

The printed name and original signature of the COMPANY's REPRESENTATIVE person approving the Supplier's and/or Sub-Supplier's ITP.

4.3.8. Discipline

This shall refer all the relevant discipline(s) involved in the ITP.

4.3.9. Location

This shall contain the general location on the WORKSITE that the ITP relates to.

4.3.10. Item No

This shall be a sequential number within each ITP starting at 1. This number shall not be duplicated within the ITP. There shall not be any sub numbering of items.

4.3.11. Activity

A description of each activity shall be included. The activities shall be sequential and shall be in order of the activity that is undertaken on a step by step basis. This provides the Inspector and Craft Supervisor with the instructions necessary to plan, coordinate, and perform the inspection of the work. Where necessary, main activities may make reference or cross refer to other ITP's. The frequency of inspection of verification shall be identified eg 100%, 50%, 10%, daily, weekly, first of batch, at delivery etc. The activity stage shall be detailed to reflect the project specifications, drawings, and contract requirements.

4.3.12. Reference Document

The Reference Document shall be the specific document that controls the activity being performed. This may be the drawing, datasheet, project specification or standard, National/International code or standard, Supplier or Sub-Supplier procedure or working practice/method. Each activity shall be allocated a reference document. No entry shall be left blank.

4.3.13. Acceptance Criteria

For each activity there shall be an acceptance criteria for the activity performed. This may be a tolerance, a reading, a value, or an outcome. The requirement/acceptance criteria is the governing document that is used to ensure that the work is fabricated/ tested correctly. The governing document is usually a procedure, project specification, data sheet and/or drawing. It may be that the governing document is more than one of these. All appropriate governing documents shall be referenced. Project specifications identified as governing documents shall indicate the paragraph where the acceptance criteria is found. The acceptance criteria for each activity shall be included.

4.3.14. Verifying Document

The verifying document is the permanent record reporting format that is used to document the activity. This may take the form of a Quality Control sign-off sheet or Inspection form and

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	18 / 26

shall become the quality record for system turnover at Mechanical Completion phase. For each activity the result of inspection, test, correction etc. shall be defined with a verifying document. For items where there is a reading or measurement of any sort taken, this shall be recorded. The appropriate Quality Control/Inspection form shall be referenced as the verifying document. Where other tests are undertaken to prove the result of an activity, these shall also be similarly recorded and the appropriate Quality Control/Inspection form shall be referenced as the verifying document. For activities involving other results, then the verifying document shall be the appropriate record generated as a consequence of the activity. No activity shall result in the verifying document being the ITP. Each activity shall have its own unique verifying document, be it a Quality Control/ Inspection form, receipt, issue request or an as-built drawing etc.

4.3.15. Supplier Responsible Person

The Supplier's responsible person shall be identified by job position, not name.

4.3.16. Inspection Mode

The Supplier or Supplier's Sub-Supplier (SUB) actually performing the work is responsible for first line Quality Control or Inspection activity. Supplier is responsible for the quality control of all work undertaken by Supplier or Supplier's Sub-Supplier(s). As a result all activities undertaken by the Sub-Supplier on behalf of Supplier shall require Supplier to undertake an inspection of the Sub-Supplier work. This is a mandatory requirement.

Where the Supplier uses a Sub-Supplier for undertaking any work, the Sub-Supplier shall be responsible for undertaking the inspection or test and generating the appropriate record. In the column identified "SUB", the Sub-Supplier shall enter "I" to signify responsible for undertaking the inspection/test or "R" as being responsible for generating the inspection record. "IR" may be entered in the "SUB" column to signify responsibility for the inspection activity and generating the record. In this instance, the Supplier shall be responsible for Verifying the record and shall enter "V" in the "Supplier" column. Verification of this activity shall require Supplier to be present at the time the inspection/test took place. An entry of "R" shall denote that the Sub-Supplier's inspector confirms the existence of an approval record supporting the indicated requirement. No inspection/test stage field shall be left blank on the ITP.

Where the Supplier does not use a Sub-Supplier for undertaking any work, the Supplier shall be responsible for undertaking the inspection or test and generating the appropriate record. In the column identified "Supplier", the Supplier shall enter "I" to signify responsibility for undertaking the inspection/ test or "R" as being responsible for generating the inspection record. "IR" may be entered in the "Supplier" column to signify responsibility for the inspection activity and generating the record. In this instance Supplier shall not be permitted to enter "V" in the "Supplier" column. An entry of "R" shall denote that the Supplier's inspector confirms the existence of an approval record supporting the indicated requirement. No inspection/test stage field shall be left blank on the ITP.

COMPANY shall denote Verification Points "V", Witness Points "W" or Hold Points "H" by entry of "V", "W" or "H".

**Supplier Quality Control
Requirement**

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	19 / 26

4.4. FABRICATION AND TESTING PROCEDURES/INSTRUCTIONS

Supplier shall submit for Contractor and/or COMPANY's review of the inspection/test procedures or instructions to the requirements of the Purchase Order within the period stipulated in the requisition. These procedures and/or instructions shall include if applicable but not limit to the following:

- Welding Procedure/Qualification
- Pre & Post Heat Treatment procedure
- Positive Material Identification Procedure
- Marking, Traceability instruction
- Hydraulic/Leakage Test procedure
- Painting Procedure
- Packing, Preservation, Shipping procedure
- Installation, Operating and Maintenance Procedure

4.5. PRE-INSPECTION MEETING (PIM)

The PIM, before fabrication of the equipment and materials and after Contractor's review of ITP, between the Supplier, Contractor and/or the COMPANY, should be held for the purpose of complete understanding by the Supplier/Sub-Supplier of specific quality requirements, if the Contractor and/or the COMPANY deem it necessary.

The Supplier shall propose date of the PIM to the Contractor, at appropriate time before fabrication is commenced. The typical agenda shall consist of:

- Scope of work / supply /service
- Supplier's documents /drawings status.
- Clarification all specific fabrication with design engineer.
- Special requirements in fabrication and Quality-Control.
- Required test(s) and acceptance criteria.
- CONTRACTOR and COMPANY witness point, hold point and inspection point.
- Record /Certificate to be reviewed.
- Record /Certificate to be contained in the manufacturer's inspection record book
- CONTRACTOR release procedure.
- Manufacturer's QA/QC system and organization.
- Inspection Schedule.
- Sub-ordered items.
- Outstanding items and instructions of CONTRACTOR.

Supplier Quality Control Requirement

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	20 / 26

In the PIM, extent and degree of the Inspector's participation in the inspection and testing shall be clarified in details and highlighted for smooth execution of onwards inspection.

4.6. INSPECTION NOTIFICATION

- 4.6.1.** The Supplier shall submit Overall Inspection and Fabrication Schedule soon after the Purchase Order. It shall be updated and submitted before the 25th of each month.
- 4.6.2.** The Supplier shall submit Monthly Inspection Schedule by the 25th of each month showing the inspection activities of next month.
- 4.6.3.** The Inspection Request shall be submitted by the Supplier to show the firm inspection dates to the Contractor at least three (3) weeks in advance by e-mail, facsimile or other appropriate methods, the form of Inspection Request will be offered by CONTRACTOR. When any change of inspection date occurs due to fabrication schedule, Supplier shall notify Contractor as needed of the revised inspection date by e-mail, facsimile or phone at least five (5) working days prior to the originally scheduled date or new inspection date, whichever is earlier.

The Inspection Request shall include the following:

- Commodity Name
- Purchase Order No. / Item No.
- Inspection Date and Time
- Inspection Location (Factory Location)
- Person in Charge
- Telephone No.
- Facsimile No. or E-mail Address

4.7. Hold Points

When hold points are specified on the approved Supplier's ITP or other applicable documents, The Supplier and/or its Sub-Supplier shall not proceed with the work until the hold point inspection has been witnessed by Contractor's Inspector or a written approval of its waiver is obtained.

4.8. Concession Request

Should it be necessary to request a concession, the Supplier shall do so by completing a "Concession/Deviation Request Form" per CONTRACTOR's format and submitting it to the Contractor for approval. Requests submitted in any other form will be automatically rejected and returned to the Supplier.

Each concession/deviation request shall be sequentially numbered and the form completed in all sections. Whether concession/deviation requests are granted or denied, all "Concession/Deviation Request Forms" shall be included as part of the Supplier Data Book.

4.9. Non-Conformity Report

The Supplier is requested to report non-conformity for product and services which do not conform to specified requirements per CONTRACTOR's format immediately, to the

Supplier Quality Control Requirement

Project No.:	01000
KUS Doc No.:	01000-PU-SPC-0003
Contr. Doc No.:	
Rev.:	R00
Page:	21 / 26

Contractor for approval, if any non-conformity is found during fabrication or inspection. In this event, the reports shall include a detail description of the condition of non-conformity and proposed disposition procedure.

4.10. Certificate of Conformance by the Supplier

The Supplier shall issue Certificate of Conformance for equipment and materials, if they:

- conform to the Purchase Order requirements,
- have no irremediable not injurious defects,
- have completed necessary fabrication / manufacturing work,
- have completed necessary documentation work.

4.11. Inspection Release by the Contractor

When the Supplier completed final inspection, the Supplier's inspection and test records, reports and certificates shall be submitted for the Contractor's review.

The Contractor will issue Inspection Release Notice to the Supplier to proceed with the shipping preparation, if the following conditions are met.

- The Supplier issued Certificate of Conformance to the Contractor and all other certificates stipulated in the Requisition/Purchase Order.
- The Supplier submitted inspection and test records and obtained the Contractor's review results.
- The required witness inspection by the approved inspection and test plan was completed.
- Non conformity was solved and approved by the Contractor.
- No deficiencies and/or pending remained unsolved.

5. DOCUMENTATION

5.1. Inspection Documents at Delivery

The Supplier, unless otherwise specified, shall deliver one copy of inspection test records together with equipment and materials so that the Contractor's site engineer can identify and trace the equipment and materials prior to installation.

5.2. Documentation

The Supplier shall submit 7 number's copies of inspection reports, test records and certificates, in hard binder, with having identification and traceability, by the time specified in the Purchase Order as a final documentation.

This includes the followings:

- (1) Supplier's Certificates of Conformance Quality Certificates
- (2) Material test certificates, with table or list traceable between the certificates and the parts, for

**Supplier Quality Control
Requirement**

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 22 / 26

a. Pressure retaining parts

b. Attachments of pressure vessel, which directly welded on the pressure retaining parts, such as reinforcing pads, parts for skirt/saddle, excluding minor parts.

c. All internal parts of alloy material and lining internals etc.

(3) Radiographic report and other NDE reports with weld map.

(4) Hydrostatic and other test reports.

(5) Mechanical test, performance/function test reports, and

(6) All other reports as specified in respective Specification

(7) Any regular reports which are mutually agreed, to be submitted.

5.2.1. In the final documentation, the Supplier shall prepare and provide Index Sheet for easy compilation and reference of all inspection and test records. This index sheet and all applicable inspection and test record forms shall be submitted to Contractor for review prior to fabrication commencement.

6. JOB SPECIFIC REQUIREMENTS

6.1. Safety Quality License for Boiler and Pressure Vessel

Suppliers of Boiler and Pressure vessels shall submit the certificate of "U" or "U2" issued by ASME, and "U" or "U2"-stamp etc. If/as it is stipulated in the Requisition/Purchase Order.

6.2. Positive Material Identification

When Positive Material Identification is specified in the Purchase Order, the Supplier shall perform alloy verification and report the results to Contractor. The parts identified shall have marking "AV" as per Purchase Order.

6.3. Welding & NDE of Pressure Vessels, Heat Exchangers, Coolers, Boilers and Heaters (Including Piping of Packaged Units)

When Specification of Welding & NDE of Pressure Vessels, Heat Exchangers, Coolers, Boilers and Heaters (Including Piping of Packaged Units) is cited in the Purchase Order, the Supplier shall comply with the welding and NDE requirements of the corresponding codes including local codes.

7. ATTACHMENTS

ATTACHMENT 1	Inspection Related Documentation
ATTACHMENT 2	Status of Sub-Ordered Material
ATTACHMENT 3	Format of Inspection and Test Plan

**Supplier Quality Control
Requirement**

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 23 / 26

ATTACHMENT 1 INSPECTION RELATED DOCUMENTATION

DOCUMENT TYPE	FOR INFORMATION	FOR REVIEW & COMMENTS	TIMING	FINAL		REMARKS
	No. Of PRINTS & TYPE			No. Of PRINTS & TYPE	TIMING	
Fabrication, Inspection, Testing, Sub-orders & Delivery Schedule	1E	-	2 weeks after order	-	-	To be kept up to dated and sent monthly
Progress Reports	1E	-	4 weeks after order	-	-	To be kept up to dated and sent monthly
Quality Control Plan / Inspection and Test Plan (ITP)	-	1 + 1E	4 weeks after order	1E	2 weeks after receipt of comments	Latest revision received and stamped "without comments" will be considered as "FINAL"
NDT and Performance Testing Procedure / Certificates	-	1 + 1E	4 weeks after order	1E	2 weeks after receipt of comments	Latest revision received and stamped "without comments" will be considered as "FINAL"
List of Sub-Suppliers	1E	-	4 weeks after order	-	-	To be kept up to dated and sent monthly. CONTRACTOR will indicate on this document which ones of the sub-orders shall be subject to inspection at source.
Copies of Agreed Sub-orders with Index	1 + 1E	-	1 week after sub- order issue	-	-	Sub-Orders for material or equipment that will be indicated by Contractor's inspector as inspect able at source shall be complete of all technical attachments applicable.
Material Verification and Test Certificates	-	-	-	2 + 3E on CD (1 hard copy to be shipped with material)	Within 2 weeks after shipment	Master copy to be ready at final inspection for Inspector's review
Quality Dossier with Index (Manufacturing & Inspection Data Books for Equipment)	-	-	-	2 + 3E on CD	Within 2 weeks after shipment	Master copy to be ready at final inspection for Inspector's review
Certificate of Conformity, Certificate of Type, Permit to Use, etc issued by the applicable Regulatory Authorities of Republic of Kazakhstan	-	1E	2 weeks before final inspection	1E	When equipment is ready for shipment	
Shipping Dimensions and Weights Transport and Lifting Drawings with Centre of Gravity (C.O.G.), Lifting Points and Weights	-	1E (see remark)	12 weeks after order	1E (see remark)	2 weeks after receipt of comments	If the drawing is bigger than A3, then 2 more hard copies shall be provided
Declaration of Conformity to the Purchase Order	-	-	-	1E	When equipment is ready for shipment	
Installation, Operation and Maintenance instruction manual as required by RoK applicable codes, rules and regulations specifically aimed at	-	-	-	1E	When equipment is ready for shipment	This manual shall particularly address the hazards connected with an incorrect use of the equipment as per applicable Code and/or Regulation.

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 24 / 26

safeguarding the safety of the personnel						
LEGENDA: E = soft file in PDF, MS Word or MS Excel format						

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 25 / 26

ATTACHMENT 2 STATUS OF SUB-ORDERED MATERIAL

EQUIPMENT.....	MAIN VENDOR.....
CUSTOMER.....	P.O. DELIVERY DATE.....
PROJECT.....	VENDOR JOB N°.....
MAIN P.O. N°.....	

[illegible]

Project No.: 01000
KUS Doc No.: 01000-PU-SPC-0003
Contr. Doc No.:
Rev.: R00
Page: 26 / 26

	DESCRIPTION OF EQUIPMENT		
	INSPECTION AND TEST PLAN		
INSPECTION AND TEST PLAN No.:		Rev. 0	Date: DD-MMM-YYYY
Requisition/Purchase Order No.:		Client: Karabatan Utility Solutions (KUS)	
Tag No.:		Project: Karabatan Power Plant	
Criticality Rating:		Project No.: 01000	
Inspection Level:			
Inspection Codes: R = Review W=Witness I = Inspect A = Approve H = Hold			

Comments: ITPs for Field Installation Plan will be finished for each piece of field installed equipment. (H) Hold Points are defined the same as (W) Witness except: the Supplier/Subcontractor may not proceed with the work beyond the Hold Point without the Inspector in attendance, except by documented Agreement from Buyer of Record. Witnessing of inspection and testing at the vessel manufacture by independent body to comply with manufacturing license shall be the responsibility of the Supplier. All costs for this activity shall be to Supplier's account. The Supplier shall provide all information/documentation required to obtain the Permits in Kazakhstan (Permit to use Foreign made Hazardous Equipment, etc.).

Date: