

TABLE OF CONTENTS

SUBSECTION-4.6 CONSTRUCTION FACILITIES

	Page. No.
SUBSECTION 4.6 CONSTRUCTION FACILITIES	2
4.6.1. SCOPE OF WORK	2
4.6.2. BUILDINGS AND AREAS	2
4.6.2.1 Construction Facilities	2
4.6.2.2 Security and Drainage	2
4.6.3. SEA AND LAND ACCESS AND CONSTRUCTION PARKING	2
4.6.4. TEMPORARY WORK	3
4.6.4.1 Removal of Soil	3
4.6.4.2 Welding	3
4.6.4.3 Temporary Water and Electricity Supply and Telecommunication Facilities	3
4.6.4.4 Temporary Sign Board	3
4.6.4.5 Temporary Staging and Scaffolding	4
4.6.4.6 Temporary Construction Road	4

SUBSECTION 4.6 CONSTRUCTION FACILITIES

4.6.1. SCOPE OF WORK

The Bidder shall optimize his erection procedure in order to minimize the laydown area and the area for prefabrication of pipe work, etc. to a minimum. It is the Bidder's responsibility to rent temporary laydown areas, etc. outside the power plant area as may be necessary in line with his erection procedure.

The Bidder shall provide all the construction facilities required, except as specified otherwise.

The Bidder shall be responsible for the availability of the necessary construction facilities in order to execute the erection and commissioning in accordance with the project schedule.

The Bidder shall submit in his Proposal a list of construction facilities provided by him, including their quantity, description and specifications of the facilities.

The design, erection and location of all the construction facilities shall be approved by the Owner.

4.6.2. BUILDINGS AND AREAS

4.6.2.1 Construction Facilities

The Bidder shall provide the construction facilities, consisting of his site office and Owner's and Engineer's site office, workshop, warehouse, laydown areas, fenced storage areas, toilet, canteen, welfare facilities, personal protective equipment, site ambulance, car parks, fence and gates, as required. The locations of the construction's facilities shall be allocated in the plot of the Muara Tawar Power Plant by the Owner.

As a minimum the Bidder shall man his office with responsible personnel to match the Owner's working hours.

4.6.2.2 Security and Drainage

The Bidder shall be responsible for the security of his own laydown areas and Bidder's temporary facilities.

The Bidder shall ensure proper drainage of the laydown area to prevent standing water for extended periods.

4.6.3. Sea and Land Access and Construction Parking

The Bidder shall ensure timely dredging of sea access channel and provision of all necessary unloading facilities for equipment arriving by sea.

Any roads or access areas which the Bidder deems necessary for access to his work shall be constructed and maintained by the Bidder at his own expense. The Bidder shall supply and maintain all required parking facilities.

4.6.4. Temporary Work

4.6.4.1 Removal of Soil

All removal or disposal soil and debris or obstruction shall be removed to outside area. Disposal area shall be responsible by the Bidder. The Bidder shall, when directed to do so by the Owner, restore at his expense any site area to its original condition that is altered or damaged.

4.6.4.2 Welding

Welding of temporary brackets, hangers, lugs etc. to structural steel or other steel surfaces for construction purposes is not permitted.

4.6.4.3 Temporary Water and Electricity Supply and Telecommunication Facilities

The Bidder shall provide and maintain the temporary water system to the necessary position in the Site for the Works. The equipment and piping of the temporary water supply system shall not obstruct the Works and the access ways. The water supply source shall be decided in consideration of his capacity, the necessary quantity for the Works and no bad environmental effects around the source.

The Bidder shall provide and maintain the temporary electricity system to the necessary position in the Site for the Works including all temporary works.

All the electricity to be used for Works whether it is inside or outside of the Site shall be paid by the Bidder.

The Bidder shall provide and maintain the temporary telecommunication facilities in the site office for the Bidder and for the Owner and the Engineer.

4.6.4.4 Temporary Sign Board

The Bidder shall provide and maintain the temporary signboard at the locations at the commencement of the works. The title shown on the signboard and the locations of the signboard shall be directed by the Owner. The material of signboard and its support shall be steel with painted finish and the foundation shall be reinforced concrete. The structure shall be strong enough against the self-weight and the wind load. The material shall be durable enough against the weather conditions. The Bidder shall provide the additional supports, or replace their unsuitable materials or locations.

4.6.4.5 Temporary Staging and Scaffolding

The Bidder shall provide and maintain the temporary staging and scaffolding at all of the necessary locations for the Works in consideration of the material transportation, construction machine access, human access and safety. The temporary staging and scaffolding shall not cause damage to any permanent structures. The Bidder shall calculate and confirm their safety, and select the suitable materials and construction method prior to setting them. The Bidder shall provide the additional supports, or replace their unsuitable materials or locations in case that they are deemed to cause damage to the permanent structures, to have lack of safety by using or instructed by the Owner.

The Bidder shall remove all the materials for the staging and scaffolding when they are not necessary to be used for the Works. The connection materials to the permanent structure shall not be remained after removal of the staging and scaffolding. The holes or damages shall be repaired after removal of the connection materials if any. The Bidder shall not remain all of the temporary materials in the Site, unless otherwise directed by the Owner.

4.6.4.6 Temporary Construction Road

The Bidder shall provide and maintain the temporary construction road necessary for the works. The temporary drainage system shall be provided and maintained during the Works. The permanent road shall not be used as temporary construction road. All materials debris or obstruction of the temporary construction road and drainage system shall be cleared from the site to the satisfaction of the Owner when they are not necessary to be used for the Works.

(Last page of Subsection 4.6)